



**PROJECT SUMMARY**

Total Facets: 33
Predominant Pitch: 8/12


Total Squares (Net): 32.33
Total Squares (19% Waste): 38.47

MEASUREMENT BREAKDOWN


Rake:	161'
Ridge:	86'
Hip:	139'
Eave:	255'
Sidewall Flashing:	92'
Valley:	137'
Headwall Flashing:	63'
Chimney Back Pan:	3'




North View




South View




East View



West View




Total Facets: 33



PITCH BREAKDOWN

Pitch	Area	Percent
8/12	18.08	56%
6/12	11.99	37%
5/12	1.56	5%
9/12	0.34	1%
10/12	0.19	1%
18/12	0.17	1%



PITCH BREAKDOWN

Pitch	Area	Percent
8/12	18.08	56%
6/12	11.99	37%
5/12	1.56	5%
9/12	0.34	1%
10/12	0.19	1%
18/12	0.17	1%



Facets: 14

Squares Without Waste: 10.1

Squares With Waste: 12

Eave: 145'

Headwall Flashing: 55'

Sidewall Flashing: 67'


Ridge: 15'

Hip: 46'

Valley: 14'

Rake: 39'

Transition: 10'



- Ridge
 Hip
 Valley
 Rake
 Eave
- Headwall Flashing
 Sidewall Flashing
 Transition

LAYER 2 DETAILS

Facets: 19

Squares Without Waste: 22.2

Squares With Waste: 26.5

Rake: 122'

Ridge: 71'

Hip: 93'

Eave: 110'


Sidewall Flashing: 25'

Valley: 123'

Headwall Flashing: 8'

Pitch	5/12	6/12	8/12	9/12	10/12	18/12
Area (sq ft)	156	1,199	1,808	34	19	17
Percent	5%	37%	56%	1%	1%	1%

Waste	0%	14%	17%	19%	21%	24%	29%
Area (sq ft)	3,233	3,685	3,782	3,847	3,911	4,008	4,170
Squares	33	37	38	39	40	41	42



Roof Area	3233 sq ft
Facets	33
Pitch	8 / 12
Chimneys	2
Ridge	86 ft
Hip	139 ft
Valley	137 ft
Rake	161 ft
Eave	255 ft
Headwall Flashing	63 ft
Sidewall Flashing	92 ft
Transition	10 ft
Chimney Back Pan	3 ft
Chimney Step	18 ft
Chimney Apron	3 ft
Counter Flashing	24 ft

Measurements rounded. Waste guidance only. Installer to verify.

		Waste	0%	14%	19%	24%
Shingle Products						
GAF Timberline HDZ	bundle		97	111	116	121
OC TruDef Duration	bundle		97	111	116	121
CertainTeed Landmark	bundle		97	111	116	121
Malarkey Vista AR	bundle		130	149	155	162
Starter Strip						
GAF Pro-Start	bundle		4	5	5	5
OC Starter Strip	bundle		4	5	5	5
CertainTeed SwiftStart	bundle		5	6	6	7
Malarkey Starter Strip	bundle		5	6	6	7
Hip & Ridge Cap						
GAF Seal-A-Ridge	bundle		10	12	12	13
OC ProEdge	bundle		7	8	9	9
CertainTeed Shadow Ridge	bundle		8	10	10	10
Malarkey EZ-Ridge	bundle		10	12	12	13
Synthetic Underlayment						
GAF FeltBuster	roll		4	5	5	5
OC ProArmor	roll		4	5	5	5
CertainTeed RoofRunner	roll		4	5	5	5
Malarkey Secure Start Plus	roll		4	5	5	5
Ice & Water Shield						
36" perimeter application (2037 sq ft)						
GAF WeatherWatch	roll		11	13	14	14
OC WeatherLock Flex	roll		10	12	12	13
CertainTeed WinterGuard	roll		11	13	14	14
Malarkey Secure Start I&W	roll		11	13	14	14
18" perimeter application (1413 sq ft)						
GAF WeatherWatch	roll		8	10	10	10
OC WeatherLock Flex	roll		7	8	9	9
CertainTeed WinterGuard	roll		8	10	10	10
Malarkey Secure Start I&W	roll		8	10	10	10

		Waste	0%	14%	19%	24%
Metals & Flashing						
Eave Drip Edge (10 ft)	piece		26	30	31	33
Rake Drip Edge (10 ft)	piece		17	20	21	22
Valley Metal W (10 ft)	piece		14	16	17	18
Step Flashing (5x7)	piece		257	293	306	319
Counter Flashing (10 ft)	piece		12	14	15	15
Headwall Flashing (10 ft)	piece		8	10	10	10
Chimney Apron (front)	ea		2	3	3	3
Chimney Back Pan / Cricket	ea		2	3	3	3
Chimney Step Flashing	piece		39	45	47	49
Chimney Counter Flash (10 ft)	piece		3	4	4	4
Ventilation						
Ridge Vent (4 ft sections)	piece		22	26	27	28
Accessories						
Coil Nails (1.25 in, 50 lb)	box		2	3	3	3
Plastic Cap Nails	box		1	2	2	2
Roofing Caulk (Tube)	tube		2	3	3	3

VENTILATION SUMMARY

Estimated Attic Area

2,716 sq ft

Footprint: 2,772 sq ft | Surface: 3,233 sq ft

Recommended Exhaust

1304 sq in

Recommended Intake

1304 sq in

NFVA Requirement

1/300

NFVA: 1304 sq in
Exhaust: 652 sq in
Intake: 652 sq in

1/150

NFVA: 2608 sq in
Exhaust: 1304 sq in
Intake: 1304 sq in

Recommended

Exhaust Options

Ridge Vent

Needed: 72' (@ 18"/lf)
Available: 75'
Capacity sufficient

Recommended

Box Vents

Needed: 27 vents
50 sq in NFA each
Total: 1350 sq in

RECOMMENDED INTAKE PRODUCTS

Product	Rating	Qty Needed
Vented Drip Edge	9 sq in/ft	145 ft
Soffit Vent	9 sq in/ft	145 ft
Bird Blocks	~3.5 sq in	373 ea

Key

 Ridge Vent

 Box Vent





Note: The estimated quantity of attic ventilation products in this report is based on the estimated attic floor area and is meant for estimating purposes only. It is the responsibility of the installer to verify the correct quantity and type of attic ventilation products prior to commencement of work. Installer must always review job-specific attic ventilation needs such as local code requirements, attic floor square footage, roof design, and conditioned spaces under the roof. GAF recommends a minimum of 1 square foot of attic ventilation (evenly split between intake and exhaust) for every 150–300 square feet of attic floor space depending on vapor barrier status. The amount of exhaust ventilation at or near the ridge must never exceed the amount of intake ventilation at or near the soffit. See gaf.com/ventcalculator for details.

ACTIVE GUTTER
255 ft
DOWNSPOUTS
10
MITER COUNTS
● Outside 90

9
● Inside 90

5
● Non-90

3
GUTTER DIAGRAM
— Run ● Out 90 ● In 90 ● Non-90

STORIES BY DIRECTION
North
2
South
2
East
2
West
2



38.47 sq · 8/12 · 33 facets

NOTES